

MAR 1 6 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION
GRAND TRAVERSE
(County)

Table with columns: Located In: (T, R, S), Corner Code # (D-11)

STATE OF MICHIGAN
GRAND TRAVERSE COUNTY
RECORDED

30 DEC 93 10:19 A.M.

KARON ANDERSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

Grid table with columns A-M and rows 2-13

I, Gary G. Wilson, in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-11: Original G.L.O. notes and witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11: No physical evidence of the original GLO witnesses were found. Found 1-1/2" iron pipe next to large stone 6" to 8" below surface on East & West fence line (measures 2639', more or less, from Southeast corner).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11: 1/4 corner common to Sections 29 & 32 Perpetuated with 2-1/2" X 30" flanged bottom galvanized iron pipe with 3-1/2" brass cap stamped GRAND TRAVERSE COUNTY REMONUMENTATION.
N40°W 40.00' iron w/RLS cap
N40°E 40.00' iron w/RLS cap
S45°E 35.00' iron w/RLS cap
S45°W 35.00' iron w/RLS cap

Corner approved by the Grand Traverse County Peer Review Group on 11-03-93.

Signed by Gary G. Wilson, PS
Surveyor's Michigan License No. 25881

December 28, 1993

