

MAR 16 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

GRAND TRAVERSE
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 27N R 11W J-9
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
GRAND TRAVERSE COUNTY
RECORDED

30 DEC 93 10:16 A.M.

KARON ANDERSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Gary G. Wilson, in a field survey on December 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-9: Original G.L.O. notes and witnesses.

G.T. Co. Road Commission records shown 1/2" iron, no date. Act 132 survey filed by Carl Roser shows iron found at "T" intersection in December 1976. In October 1987, Act 132 survey by Gosling Czubak & Assoc. shows iron found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9: No physical evidence of the original GLO witnesses were found.

Found 1" iron bar in monument box in centerline of Hammond Road and LaFranier Roads (paved) which matched Gosling Czubak & Assoc. witnesses from 1987.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9: 1/4 corner common to Sections 23 & 26

Perpetuated with 2-1/2" X 30" flanged bottom galvanized iron pipe with 3-1/2" brass cap stamped GRAND TRAVERSE COUNTY REMONUMENTATION.

- S40°E 39.76' Power Pole
- S45°W 35.85' Power Pole
- N56°W 80.50' 14" Elm
- N78°E 99.53' 22" Maple

Corner approved by the Grand Traverse County Peer Review Group on 12-15-93.

Signed by Gary G. Wilson
 Gary G. Wilson, PS
 Surveyor's Michigan License No. 25881

Date December 28, 1993

