

MAR 16 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
GRAND TRAVERSE
(County)

Located In:	Corner Code #
27N 11W	K-10
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

STATE OF MICHIGAN
GRAND TRAVERSE COUNTY
RECORDED
30 DEC 93 10:16 A.M.
KARON ANDERSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, **Gary G. Wilson**, in a field survey on **December 17**, 19 **93**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-10: Original G.L.O. notes and witnesses.
In September 1879, stone noted, no marks (per Liber 11, Pg. 90). In May 1915, E.P. Waterman noted and witnessed corner in highway survey (per Liber 6, Pg. 20). G.T. Co. Road Commission records of 1955 show iron found which matches Waterman witnesses. Act 132 surveys by Perla Stout & Assoc. filed in Feb. 1972 and May 1973 show iron found in monument box. Act 132 surveys by W. Batzer show 5/8" iron in monument box in March 1976 and an iron found in September 1978.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10: No physical evidence of the original GLO witnesses were found.
Found iron in monument box in centerline of Garfield and Birmley Roads (paved). Witness checked to the corner of the old schoolhouse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10: 1/4 corner common to Sections 25 & 26
Perpetuated with 2-1/2" X 30" flanged bottom galvanized iron pipe with 3-1/2" brass cap stamped **GRAND TRAVERSE COUNTY REMONUMENTATION.**

S64°E 81.24' Tel. Pole
N50°E 78.28' Power Pole
N45°W 75.10' Tel. Pole
S53°W 46.65' Power Pole



Corner approved by the Grand Traverse County Peer Review Group on 12-15-93.

Signed by Gary G. Wilson, PS Date December 28, 1993
Surveyor's Michigan License No. 25881