

MAR 1 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

GRAND TRAVERSE

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 27N R 11W K-11
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

STATE OF MICHIGAN  
GRAND TRAVERSE COUNTY  
RECORDED

30 DEC 93 10:17 A.M.

KARON ANDERSON  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gary G. Wilson, in a field survey on December 17, 19 93,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-11: Original G.L.O. notes and witnesses.

In November 1893, E.H. Allyn found old stake in road with irons around it (per Liber 1, Pg. 401 and Liber 11, Pg. 186); in 1903 he found post in road (per Liber 3, Pg. 232) and in September 1905 he found a stake with an iron sleigh shoe, set gray granite (15x8x6) in pit of cobble stones (per Liber 2, Pg. 110; Liber 10, Pg. 273 and Liber 13, Pg. 50). In August 1914 corner was used in survey of Road. In April 1967, Consumers Power Co. survey by P. Perla shows iron in monument box. Act 132 surveys filed by Gourdie/Fraser & Assoc. in March 1973 and June 1975, by Perla Stout & Assoc. in September 1973 and Grand Traverse Surveying Co. in November 1992 show monument box and witnesses check with Consumers Power Co. survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11: No physical evidence of the original GLO witnesses were found.

Found 1" iron pipe in monument box, 1 foot West of centerline of Rusch Road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11: Corner common to Sections 25, 26, 35 & 36

Perpetuated with 2-1/2" X 30" flanged bottom galvanized iron pipe with 3-1/2" brass cap stamped GRAND TRAVERSE COUNTY REMONUMENTATION.

- N71°W 47.75' Power Pole
- S68°W 84.75' Block foundation Hse. #997
- S42°E 46.18' Power Pole
- N34°E 103.60' Power Pole

Corner approved by the Grand Traverse County Peer Review Group on 12-15-93.

Signed by Gary G. Wilson  
Surveyor's Michigan License No. 25881

Date December 28, 1993

