

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
GRAND TRAVERSE
 (County)

Located In: Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>27N</u> | R | <u>11W</u> | <u>L-7</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

STATE OF MICHIGAN
 GRAND TRAVERSE COUNTY
 RECORDED

30 DEC 93 10:17 A.M.

KARON ANDERSON
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gary G. Wilson, in a field survey on December 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original GLO witnesses: 8" Cedar N45°W 4 chains
 12" Tamarack S73°E 11 chains
 In April 1911, E.P. Waterman found old stake with remains of both U.S. witnesses (per Liber 2, Pg. 404 and Liber 10, Pg. 90).
 In November 1976, a Gosling, Czubak & Assoc. Act 132 survey shows iron found. In November 1981, the plat of Airport Industrial Park No. 2 shows corner as P.O.B. of plat.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7: No physical evidence of the original GLO witnesses were found.
 Found concrete monument at edge of stream in water that fits location shown on plat of Airport Industrial Park No. 2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7: 1/4 corner common to Sections 13 & 24
 2-1/2" X 30" flanged bottom galvanized iron pipe with 3-1/2" brass cap
 COUNTY REMONUMENTATION.
 S42°W 17.74' 8" White Birch
 N39°W 25.83' 6" Maple
 N66°E 28.84' 10" Poplar
 N77°W 19.21' 8" White Birch

stamped GRAND TRAVERSE



Corner approved by the Grand Traverse County Peer Review Group on 12-15-93.

Signed by Gary G. Wilson
 Gary G. Wilson, PS
 Surveyor's Michigan License No. 25881

Date December 28, 1993