

MAR 15 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: GRAND TRAVERSE (County), Located In: (Town/Range), Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

STATE OF MICHIGAN
GRAND TRAVERSE COUNTY
RECORDED
30 DEC 93 10:15 A.M.
KARON ANDERSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked in cell J9.

I, Gary G. Wilson, in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9: Original G.L.O. notes and witnesses.

In May 1973, Act 132 survey by Perla Stout & Assoc. show iron set. In November 1975, Act 132 survey by W. Batzer shows 5/8" iron found and culvert witness checks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9: No physical evidence of the original GLO witnesses were found.

Found 5/8" re-bar in monument box in centerline of Hammond Road (paved). witness to culvert matches.

Old fence lies to North and

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9: 1/4 corner common to Sections 24 & 25

Perpetuated with 2-1/2" X 30" flanged bottom galvanized iron pipe with 3-1/2" brass cap stamped GRAND TRAVERSE COUNTY REMONUMENTATION.

- S08°E 32.18' "X" in S. end of conc. culvert
N05°W 37.00' 12" Poplar
N78°E 114.30' 8" Tamarack
S70°E 112.00' Power Pole

Corner approved by the Grand Traverse County Peer Review Group on 12-15-93.

Signed by Gary G. Wilson, PS
Surveyor's Michigan License No. 25881

Date December 28, 1993

