

MAY 07 1997

LIBER 1803 HA 734

## COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN **GRAND TRAVERSE COUNTY** DUCHDOOR

For corners in			MECONDED
Grand Traverse (County)	Located In:	Corner Code #	30 Mec 96 12:25 P.H.
1. Public Land Survey	T <u>28N</u> R <u>9W</u> T R T R T R		KARON ANDERSON REGISTER OF DEEDS
2. Property Controlling	s T R	4400	
in Section	S T R		
3. Miscellaneous	S T R		•
Property in Section	S T R		Register of Deeds Stamp & File Number
4. Lot No, R	ecorded Plat		
5. Private Claims			A B C D E F G H I J K L M
do hereby certify that under requirements 1 and 2 above were in commanual of survey instructions Management or by a decree of 5 above were in conformance of Decree of a Court of Law; estate as expressed below:  NOTE: Not more than 4 coron this certificate.	onformance with regulations and most the United States Departmance a Court of Law and/or that the cowith the rules of the Michigan Bookished, re-established, monument the rules and the same town and the same to	A. of 1970, the corner points menticules therefore as required in the curent of the Interior, Bureau of Lurner points mentioned in lines 3, 4 and of Professional Surveyors or I ted, re-monumented, recovered, for range, may be recorded	rent ,
A. Description of original r	nonument and accessories a	nd/or subsequent restoration:	
pipe with 3 1/4'	' brass Cap GRAND TRAV Bast & West black to	ERSE COUNTY REMONUMENTS	x 30" flanged bottom galvanized iron ATION, in a monument box 2" below the averse Co. Remonumentation Land Cor Traverse Co.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- See Cor common to Secs 7, 8, 17 & 18, T28N-R9W; The Grand Traverse Co. Remonumentation Cor had been removed by road construction, however fd a 1/2" rerod in a stone pile that apparently had been placed by the Rd. Comm. Surveyors at some time during the Bates Rd. reconstruction project. The rerod position agrees with the wits of record and the Remon LCR recorded in L.3, Pg.630, and a 2 1/2" x 30" galvanized iron pipe with a 3 1/4" brass Cap stamped GRAND TRAVERSE COUNTY REMONUMENTATION, in a monument box, 3" below the surface of the North-South, East-West road intersection, was placed at the record position, and is accepted as a careful and faithful remembershipment of the position of the original Remon Cor. C-51
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: C-5) Sec Cor common to Secs Secs 7, 8, 17 & 18, T28N-R9W;

A 2 1/2" x 30" flanged bottom galvanized iron pipe with a 3 1/4" brass Cap stamped GRAND TRAVERSE COUNTY REMONUMENTATION, in a monument box, 4" below the surface of a North-South, East-West black top road intersection.

OF BICHIE

SURVEYOR

No.

AND GO

284

N51°W - Power Pole - 51.36' N51 W - Power Pole - 51.56 S31 E - Power Pole - 60.47' S74 E - Power Pole - 145.46' N80 E - Power Pole - 144.43'

**UNANIMOUSLY ACCEPTED BY THE** GRAND TRAVERSE COUNTY PEER REVIEW GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1000 AT A MEETING ACT 345 OF 1990 AT A MEETING
HELD ON 12-13
ROBERT F. MITCHELL P.S., CITAINNE

JP.S., CHÂÌHVÂN

Date

Signed by Surveyor's Michigan License No.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1071 REVISED MAY 14, 1975 REVISED JAN., 1983