

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 28 ^{N.} R. 9 ^{W.}	C-1; C-2; C-3
2. PROPERTY CONTROLLING IN SECTION	T. _____, ^{N.} ^{S.} , R. _____, ^{E.} ^{W.}	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____, ^{N.} ^{S.} , R. _____, ^{E.} ^{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 31, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-1 Fd. mon. per M.S.H.D. (1955) survey who fd. a 4"x4" cedar stake per C.O.Carver survey in 1937, Liber 8, page 105, Gr. Trv. Co. Register of Deeds. Also see Final Survey Map and Report at Mich. Dept. of Natural Resources, Roscommon, Michigan, Survey Project No. 77-18.
- C-2 Fd. mon. per M.S.H.D. 1963, who fd. 1/2" pipe which perpetuated Hodgman's, Steele's and Waterman's position.
- C-3 Fd. large stone with cross on top as recovered by Hodgman, Steele, Waterman, M.S.H.D. and DeLaMater.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1	C-2	C-3
Fd. bronze capped "State of Mich." mon. & set cedar post w/loc. tag	Fd. bronze capped "State of Mich." mon. & set cedar post w/loc. tag	Fd. large stone w/cross on top & set cedar post w/loc. tag
14" Oak N14 ^{OW} 28.53	13" W. Pine S19 ^{OW} 20.78	12" Cedar S55 ^{OW} 9.30
13" Oak N56 ^{OW} 12.65	22" W. Pine S38 ^{OE} 7.37	8" Hemlock N59 ^{OW} 43.42
17" Oak N78 ^{OE} 18.57	Fd. 18" W. Pine N05 ^{OW} 30.77	10" Cedar N04 ^{OW} 51.59
	Fd. 19" W. Pine N83 ^{OE} 53	1/2 BT Rd. Due W 95'±

SIGNED BY Carl F. Roser 4-10-78 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

ACME TOWNSHIP
GRAND TRAVERSE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____