

**SURVEY &  
REMONUMENTATION**

**FEB 26 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Leelanau  
(County)

Located in:

Corner Code #

1. Public Land Survey

T 28NR 11W

A-6(Elmwood Twp)

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling  
in Section

S \_\_\_

T \_\_\_ R \_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_

T \_\_\_ R \_\_\_

S \_\_\_

T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Steven P. Bye, in a field survey on December 10, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-6: West 1/4 corner of Section 18

G.L.O. notes: set 1/4 post - Sugar 24 S32W 19 lks.  
Hemlock 15 S40E 37lks.

1948 H. H. Brehmer field book 10 - i.p at corner

1973 Glenn Delamater found 3/4" iron & filed L.C.R.C. #64

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6: West 1/4 corner of Section 18

3/4" i.p. found on side slope at westerly side of Ma nn Road.

Delamater witnesses

18" ash N80°W 71.49'  
Tele. pole S55°W 105.50'  
Guy pole N45°E 142.88'  
12" walnut S45°E 79.80'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6: West 1/4 corner of Section 18

3/4" iron pipe accepted as the best available evidence of the position of the original corner by the Leelanau County Remonumentation Peer Review Group on November 17, 1997 and replaced with a 3/4" galvanized iron pipe 3' long with a brass cap.

Witnesses: 18" ash N80°W 71.49'  
Guy pole N45°E 142.88'

Tele. pole S55°W 105.50'  
12" walnut S45°E 79.80'

Signed by Steven P. Bye  
Surveyor's Michigan License No. 35991

Date 12-12-97

Barbara Kirt 12/30/97  
Leelanau Res of Deeds 2:12 PM  
BJK Fees 9.00  
04800002 P0202 Page 1 of 1

#504

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		13		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**APPROVED LAND CORNER  
P.A. 345 OF 1990  
LEELANAU COUNTY**

DATE: 11-17-97  
COUNTY REP. [Signature]

