

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF LEELANAU
RECEIVED FOR RECORD

1993 DEC 28 PM 4: 25

For corners in
Leelanau

(County)

Located In:

Corner Code -#

- 1. Public Land Survey T 28N R 11W C-2
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Barbara Kirt
REGISTER OF DEEDS

FILE #333

LIBER 2 PAGE 30

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. A dot is marked at row 2, column C.

I, Steven P. Bye, in a field survey on December 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-2: E 1/4 corner, Section 6: G.L.O. "Set 1/4 section post" Beech 9, N 74 E, 32 links Sugar 14, S 24 W, 38 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-2: E 1/4 corner, Section 6: Found 1" diameter 16" iron bar fitting witnesses of record. Wm. B. Batzer Jr. set this iron bar by single proportion between C-1 and C-3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-2: E 1/4 corner, Section 6: Found 1" diameter iron bar accepted by the Leelanau County Remonumentation Peer Group, November 29, 1993, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap - set 4" below surface

- Basswood group - Northeast 61.82'
10" cherry - S 40 E, 47.90'
9" cherry, S 35 W, 59.20'
9" poplar - N 80 W, 209.75'

Signed by Steven P. Bye

Date 12-20-93

Surveyor's Michigan License No. 35991

