

MAY 16 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Leelanau
(County)

Located In:

Corner Code #

Barbara Kirt

01/08/97

Leelanau Rec of Deeds

2:26 PM

BJK

Fee:

9.00

04600002 P0153

Page 1 of 1

- 1. Public Land Survey T 28N R 11W E-5
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Section S T R

#456

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5				●								
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Steven P. Bye, in a field survey on October 23, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-5: Southeast corner of Section 8
G.L.O. - set post corner to Section 8, 9, 16 & 17
 Beech 10 N16E 22 lks.
 Beech 18 S25W 65 lks.
Square stake in stones found (Brehmer 1941) and replaced with a concrete monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5: Southeast corner of Section 8
Square stake in stones found (Brehmer 1941) and replaced with a concrete monument.
Square concrete monument found (Batzer Jr. 1973)
Batzer Jr. witnesses:
6" Maple N21°E 31.06'
8" Maple N16°W 17.80'
Twin 6" Oak S74°E 13.05'

APPROVED LAND CORNER
P.A. 345 OF 1990
LEELANAU COUNTY

DATE: 10-23-96
COUNTY REP. N.M. O'Non

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5: Southeast corner of Section 8
Square concrete monument accepted as a careful and faithful re-establishment of the position of the original corner by the Leelanau County Remonumentation Peer Review Group, October 23, 1996 and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap.
6" Maple N21°E 31.06'
8" Maple N16°W 17.80'
Twin 8" Oak S74°E 13.05'
8" Oak S54°W 5.63'



Signed by Steven P. Bye
Surveyor's Michigan License No. 35991

Date 12/26/96