

**SURVEY &  
REMONUMENTATION**

**MAR 15 2000**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Leelanau</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>11W</u>	<u>E-8</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Barbara Kirt 12-29-99  
Leelanau Rec of Deeds 4:02 PM  
BJK Fee: 9.00  
04B00002 P0339 Page 1 of 1

#642

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Victoria A. Brown, in a field survey on December 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
E-8: Quarter corner common to Sections 20 and 21.  
G.L.O. notes: Set 1/4 section post at 40.00 chains  
15" Beech, N35°W, 31 links  
20" Hemlock, S50°E, 34 links  
Greene (1918) County Surveyor notes - Corner in RR right of way. At 80 chains from W 1/4 post, set stake in correct position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
E-8: Quarter corner common to sections 20 and 21.  
Found iron pipe in old R/R right of way (P. Perla-1968). Used by Gourdie/Fraser in 1972 and R.M. Harris.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
E-8: Quarter corner common to sections 20 and 21.  
Found 3/4" iron pipe, 15' west of centerline of asphalt trail. 3/4" iron pipe accepted as the best available evidence of the position of the original corner by the Leelanau County Remonumentation Peer Review Group on December 8, 1999 and remonumented with a 3/4" galvanized iron pipe, 3' long, with a brass cap.

Existing Witnesses:  
7" Ash, S72°E, 35.04'  
7" Elm, N72°E, 27.55'  
7" Cherry, N21°E, 37.49'  
9" Ash, N71°E, 57.19'

**APPROVED LAND CORNER  
P. A. 345 OF 1990  
LEELANAU COUNTY**  
DATE: 12-8-99  
COUNTY REP. [Signature]



Signed by Victoria A. Brown  
Surveyor's Michigan License No. 40158

Date 12/27/99