

APR 26 1996

103 651

218

950326

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
GRAND TRAVERSE COUNTY  
RECORDED

29 DEC 95 9:52 A.M.

KARON ANDERSON  
REGISTER OF DEEDS

For corners in  
Grand Traverse  
(County)

Located In: Corner Code #

1. Public Land Survey	T	29N	R	10W	G-5
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Gary G. Wilson, in a field survey on December 12, 1995,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-5 Corner common to Sections 9, 10, 15 & 16  
County Surveyor records: S. C. Hodgeman (1882) referenced distance North to 1/4 cor. at 2714.58 ft. C.P. Tuller stone with "x" 3 ft. deep, October, 1890.  
E.P. Waterman dug for stone and could not locate, November, 1908. Distance North to 1/4 corner is 2714.58 ft. per S.C. Hodgeman. Distance West to 1/4 corner is 2566.7' per Hodgeman. Referenced road centerline.  
Saywer found square iron in road intersection in March, 1950.  
Act 74 records: Wm. Richards filed L.C.R. Found 1/2" iron pipe in Monument Box in intersection of centerlines of Peninsula Drive and Kroupa Road.  
Distance West 2566.36'; distance North 2710.88' per Richards survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 Corner common to Sections 9, 10, 15 & 16  
Found 1/2" iron pipe in monument box at intersection of centerlines of Kroupa Road and Seven Hills Road.

Accepted as a careful and faithful perpetuation of the position of the original corner.

UNANIMOUSLY ACCEPTED BY THE  
GRAND TRAVERSE COUNTY PEER  
REVIEW GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC  
ACT 346 OF 1990 AT A MEETING  
HELD ON 12-11-95

RFM  
ROBERT F. MITCHELL, P.S., Chairman



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5  
Section corner common to Sections 9, 10, 15 & 16  
Perpetuated with 2-1/2" x 30" flanged bottom galvanized iron pipe with 3-1/2" brass cap stamped GRAND TRAVERSE COUNTY REMONUMENTATION.

N72°E 72.83' 6" Cherry  
S32°E 76.14' 6" Cherry  
S45°W 133.54' Power Pole  
N47°W 79.83' Power Pole

Corner approved by the Grand Traverse County Peer Review Group on December 11, 1995.

Signed by Gary G. Wilson  
Surveyor's Michigan License No. 25881

Date 12-27-95