

STATE OF MICHIGAN
 COUNTY OF LEELANAU
 RECEIVED FOR RECORD

1995 DEC 29 PM 2:09

Barbara Kirt
 REGISTER OF DEEDS

#430

LIBER 2 PAGE 127

Register of Deeds Stamp & File Number

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Leelanau
 (County)

Located In:	Corner Code #
T29NR11W	A-2
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Nicholas M. O'Non, in a field survey on Nov. 29, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 A-2: West 1/4 Corner of Section 6.
 G.L.O. Notes: Set 1/4 Post, per Orange Risdon Survey of October 23, 1850.
 Sugar 12", North, 19 Links
 Lynn 12", S 08° W, 13 Links

APPROVED LAND CORNER
 P.A. 345 OF 1990
 LEELANAU COUNTY
 DATE: 7-12-95
 COUNTY REP. N.M. O'Non

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 A-2: West 1/4 Corner Section 6.
 Found 5/8" iron rod per Perla and Stout, P.C. survey recorded in Liber 1 of Surveys, page 455.
 Power Pole, N 14° W, 141.23'
 4" Twin Aspen, S 40° E, 74.93'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-2: West 1/4 Corner of Section 6.
 5/8" iron rod accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Review Group on July 12, 1995.
 Replaced with a 3/4" by 3.0' long galvanized iron pipe with stamped brass cap in pavement box.
 Power Pole, N 07° W, 143.22'
 NW Cor. of House, S 86° E, 92.84'
 14" Apple, S 34° E, 74.79'
 Power Pole, S06° E, 182.36'

Signed by *Nicholas M. O'Non*
 Surveyor's Michigan License No. 28420

Date 12-29-95

