

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF LEELANAU
RECEIVED FOR RECORD

1993 DEC 28 PM 4: 26

Barbara Kirt
REGISTER OF DEEDS

FILE #336

LIBER 2 PAGE 33

Register of Deeds Stamp & File Number

For corners in

Leelanau

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>29N</u> R <u>11W</u> | <u>D-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steven P. Bye, in a field survey on December 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

D-1: N 1/4 corner Section 5 G.L.O. "Set 1/4 section post"
Beech 16 N 50 W 42 links
Sugar 14 S 38 E 16 links

County Surveyor's notes: Stone 1.3 feet North of fence corner of fences N & S and West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1: N 1/4 corner Section 5 Granite stone found 1.3 feet North of E-W fence line

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1: N 1/4 corner Section 5 Granite stone found, used high point. Accepted by the Leelanau County Remonumentation Peer Review Group, November 29, 1993, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap.

- 7" red pine - N 15 W, 5.86'
- 6" red pine - N 50 E, 7.76'
- 7" red pine - S 60 E, 31.80'
- 6" red pine - S 10 W, 44.22'

Signed by

Steven P. Bye

Date

12-20-93

Surveyor's Michigan License No.

35991

