

MAY 16 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Leelanau (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>29N</u>	R	<u>11W</u>	<u>F-3</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Leelanau Res of Deeds
 BJK Fee: 9.00
 04500002 P0160 Page 1 of 1

#463

Register of Deeds Stamp & File Number

I, Steven P. Bye, in a field survey on October 29, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-3: South 1/4 corner of Section 4
 G.L.O. notes:
 "Set 1/4 section post"
 Sugar 24 N17W 39 links
 Do. 20 S2E 50 links

APPROVED LAND CORNER
 P.A. 345 OF 1990
 LEELANAU COUNTY

DATE: 10-23-96
 COUNTY REP. M. M. O'Neil


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3: South 1/4 corner of Section 4
 5/8" iron bar found. This corner was set by Theodore Weinert between monuments East-West and on a fence line North
 5/8" iron bar found by O'Neil (1986)
 Witnesses:
 Power Pole N4°E 97.43'
 Power Pole N71°E 84.85'
 7" Ash S55°E 69.18'
 1.4 feet North of the centerline of Revolt Road on fenceline North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3: South 1/4 corner of Section 4
 Found 5/8" iron bar and accepted as the best available evidence of the position of the original corner by the Leelanau County Remonumentation Peer Review Group, October 23, 1996, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap and protective monument box.
 Existing witnesses:
 Power Pole N4°E 97.43'
 Power Pole N71°E 84.85'
 7" Ash S55°E 69.18'
 New Witnesses:
 Power Pole N4°E 98.03' (6' High)
 Power Pole S4°W 136.95' (2' High)
 7" Ash S55°E 69.25' (5' High)
 Power Pole N71°E 84.92' (4' High)

Signed by Steven P. Bye
 Surveyor's Michigan License No. 35991



Date 12/27/96