

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF LEELANAU
RECEIVED FOR RECORD

1993 DEC 28 PM 4: 26

Barbara Kist
REGISTER OF DEEDS

FILE #335

LIBER 2 PAGE 32

Register of Deeds Stamp & File Number

For corners in

Leelanau

(County)

Located In:

Corner Code =#

- 1. Public Land Survey T 29N R 11W H-1
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Steven P. Bye, in a field survey on December 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-1: N 1/4 corner Section 3: G.L.O. "Set 1/4 section post"
 Beech 12 N 58 W 50 links
 Beech 10 N 06 E 33 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1: N 1/4 corner Section 3: 5/8" iron rod found 2.8' South of centerline McAllister Rd.
 This corner was set by Theodore H. Weinert, November 7, 1974. He set it "33' North of found stone per record" on same line as found stone at center post. The County surveyor's notes state, "2 rods South of N 1/4 post drove section of sled shoe 2-1/2" wide 30" long"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1: N 1/4 corner Section 3: 5/8" iron rod accepted by the Leelanau County Peer Review Group November 29, 1993, and replaced with a 3/4" i.d. galvanized pipe 3' long with a brass cap.

Signed by *Steven P. Bye*
 Surveyor's Michigan License No. 35991

Date 12-20-93

