

SEP 17 1999

231

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

APPROVED FOR FILING
P.A.
Houghton County

4/5/95

RW Comps

For corners in

HOUGHTON

(County)

Located in:

Corner Code #/:

1. Public Land Survey

T 47N R 37W

M-12

T R

T 47N R 36W

A-12

T R

T R

2. Property Controlling
In Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

REGISTER'S OFFICE

Houghton County, Mich.

Received for record the...
of... A. D., 1995, at...
o'clock... A.M. and recorded in Vol. ...
of... Page...
...
Register

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

1/4 Corner, Sections 36, 31; T47N., R.37-36W.

I, Richard L. Drahn, in a field survey on December 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt, U.S. Deputy Surveyor; on June 17, 1847. Original bearing trees:

Hemlock	20"	S.20°E.	10 links	(6.60 feet)
Hemlock	18"	N.08°W.	17 links	(11.22 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing trees found. Re-established corner position by single proportion measure on line between the N.E. and the S.E. corner of Section 36, T.47N., R.37W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a standard 2" diameter by 30" long split base aluminum monument with a 3/4" aluminum cap stamped to read: T.47N., R.37-36W.; 1/4; S.36, S.31; 1993; R.L.S. 21564: from which I established the following new blazed and scribed bearing trees and/or reference objects:

14"	Sugar Maple	N.89°W.	13.95 feet
14"	Sugar Maple	N.17°E.	13.12 feet
10"	Sugar Maple	S.21°E.	11.18 feet

A 6' steel sign post bears: S.35°W., 1.00 feet.



Signed by Richard L. Drahn

Date February 11, 1994

Surveyor's Michigan License No. 21564

U.S.F.S. X-25