

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

335

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47N</u> N. S., R. <u>36W</u> E. W.	B3
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER'S OFFICE
 Houghton County, Mich.
 Received for record the...
 of...
 A. D., 19... at...
 o'clock... M. and recorded in Vol...
 of...
 Page...
 R. Register

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on May 15, 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
One Quarter Corner common to sections 6 and 7 of T47N R36W

1851 survey by E.C. Martin Deputy Surveyor, Set Cedar Post, (1) S.Maple 12 S45W 20 links,
 (2) R.Maple 8 N45E 10 links
 1973 search by U.S.F.S. did not turn up any evidence of the corner.

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Houghton County
Nov. 13, 1996
Robert W. Camp

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 I searched for but could not find evidence of the original survey. I recovered this corner position by single proportionate measurement between the Southwest and Southeast corners of Section 6. The GLO calls do not aid in recovery of this corner. I could find no conflicting information that would lead to another location. This position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
One Quarter Corner common to sections 6 and 7 of T47N R36W

Monu. Set a 2"x30" flared base aluminum pipe with 3 1/4" aluminum cap and magnet.
 Witnesses:
 8d nail in the southwest side of a R.Maple 3" N42W 10.33 feet
 60d nail in the north side of a R.Maple 5" S72E 22.23 feet
 60d nail in the east side of a R.Maple 6" S22E 17.94 feet
 8d nail in the south side of a R.Maple 4" S76W 27.12 feet
 SW corner of Section 6 West 2426.10 feet
 SE corner of Section 6 East 2644.97 feet

BUREAU &
 MONUMENTATION
 MAY 16 1997
 REGISTRATION

SIGNED BY Patrick R. Leemon DATE May 15, 1996

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____