

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Houghton  
(County)

Located in:

Corner Code: *77*

- 1. Public Land Survey T 47N R 36W  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

B-11

REGISTER'S OFFICE

Houghton County, Mich.

Received for record the *25* *26*  
of *April* A. D., 19*95*, at *8:00*  
o'clock, *P.* M. and recorded in Vol. *3*  
of *Deeds* Page *123*  
*W. J. ...* Registrar

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
- 5. Private Claims  
1/4 Corner Sections 30 & 31; T.47N., R.36W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

*Richard L. Drahn* in a field survey on *May 16,* 19*94*  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by E.C. Martin, U.S. Deputy Surveyor, on September 15, 1851.

Original bearing trees:

Y. Birch	10"	S.40E.	15 links	( 9.90 feet.)
Maple	16"	N.44W.	34 links	(22.44 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of the original survey remains. Re-established corner position on line  
between and proportionate distance from the northeast and northwest section corners  
of Section 31; T.47N., R.36W.

SURVEY &  
REMONUMENTATION

MAY 16 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position and 6" below the surface of an E-W road; I set a 2" I.D. by 12"  
long concrete filled galvanized iron pipe with a 3" circular brass cap stamped to read:  
T.47N., R.36W; 1/4; S-30, S-31; 1994; R.L.S. 21564 from which I established the following:  
Standard Aluminum Reference Monument North, 7.93 feet

8"	Sugar Maple	N.03W.	26.62 feet
12"	Sugar Maple	S.03W.	25.58 feet
10"	Sugar Maple	S.29W.	30.39 feet
6'	Steel Rail	N.01E.	8.94 feet



Signed by *Richard L. Drahn*

Date February 7, 1995

Surveyor's Michigan License No. 21564