

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

HOUGHTON
(County)

Located In:

Corner Code #1

- 1. Public Land Survey T 47N R 36W B-13
- 2. Property Controlling S T R
- 3. Miscellaneous S T R
- 4. Lot No. Recorded Plat
- 5. Private Claims

REGISTER'S OFFICE

Houghton County, Mich.

Received for record the 25 day of April A. D., 1995 at 3 o'clock A. M. and recorded in Vol. 301 of R.L.S. Page 201

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Richard L. Drahn, In a field survey on December 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt, U.S. Deputy Surveyor, on September 22, 1846. Original bearing trees:

- Yellow Birch 14" N.60°E. 11 links (7.26 feet)
- Yellow Birch 14" N.52°W. 24 links (15.84 feet)

S. J. Stahl, Timber cruiser in 1933, found scribing on the NE bearing tree, and set a 5" x 5" x 40" square cedar post at the corner position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Correct corner position found marked by the 5" x 5" x 40" square cedar post set by S. J. Stahl. Found a stump hole with decayed yellow birch bark at N.52°W, 24 links. Distance checks to natural feature ties East and West.

SURVEY & REMONUMENTATION

MAY 16 1997

REGISTRATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a standard 2" diameter by 30" long split base aluminum monument with a 3 1/2" aluminum cap stamped to read: T.47-46N., R.36W.; 1/4; S.31, S.6; 1993; R.L.S. 21564; from which I established the following new blazed and scribed bearing trees and/or reference objects:

- 8" Aspen N.14°E. 14.77 feet
- 20" Sugar Maple S.23°E. 29.02 feet
- 6" Sugar Maple S.89°W. 14.64 feet

A 6' steel sign post bears: S.09°E. 0.58 feet



Signed by Richard L. Drahn

Date February 16, 1994

Surveyor's Michigan License No. 21564

U.S.F.S. Z-3