

233

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

4/5/95
 RW Camps
 For corners in
 HOUGHTON Iron
 (County)

Located in: Corner Code #

1. Public Land Survey	Houghton	47N	R	37W	M-13
		T 47	R	36	M-01
	Iron	T 46	R	37	A-13
		S 46	R	36	A-01
2. Property Controlling In Section		S	T	R	
3. Miscellaneous Property in Sec.		S	T	R	

REGISTER'S OFFICE
 Houghton County, Mich.
 Received for record the 25th day
 of April, A. D., 1995, at 8:00
 o'clock, P. M. and recorded in Vol. 3
 of Land Books, Page 233
 R. L. Drahn, Registrar
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 Section Corner, Sections 36, 31, 1, 6; T.47-46N., R37-36W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													


Richard L. Drahn, in a field survey on December 6, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below: Southeast Township Corner of T.47N., R.37W.
 NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Corner established by John Burt, U.S. Deputy Surveyor, on September 22, 1846. Original bearing trees:
 Y. Birch 24" S.57°E. 12 links (7.92 feet)
 Sugar 20" N.60°W. 46 links (30.36 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Restored corner position by retracement measurement from recovered corners and from natural features; north, south, east and west.

SURVEY &
 REMONUMENTATION
 JUL 31 1995
 COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 At the corner position I set a standard 2" diameter by 30" long split base aluminum monument with a 3 1/4" aluminum cap stamped to read: T.47-46N., R.37-36W.; S.36, S.1, S.31, S.6; 1993; R.L.S. 21564: from which I established the following new blazed and scribed bearing trees and/or reference objects:
 10" Sugar Maple N.46°W. 23.62 feet
 10" Sugar Maple N.11°W. 18.80 feet
 10" Sugar Maple N.31°E. 20.43 feet
 A 6' steel sign post bears: South 0.73 feet.



Signed by Richard L. Drahn Date March 2, 1994
 Surveyor's Michigan License No. 21564