

219

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Houghton (County)

Located in:

Corner Code #

- 1. Public Land Survey
 - T _____ R _____
 - T _____ R _____
 - T _____ R _____
 - T _____ R _____
- 2. Property Controlling in Section
 - S 30 T 47N R 37W
 - S _____ T _____ R _____
- 3. Miscellaneous Property in Sec.
 - S _____ T _____ R _____
 - S _____ T _____ R _____

B-10

REGISTER'S OFFICE
Houghton County, Mich. 35.
Received for record the 25th day
of April, A. D., 1995, at 8:11
o'clock P. M. and recorded in Vol. 3
Page 219
Register

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims
C 1/4 Corner, Section 30; T.47N., R.37W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	28	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard L. Drahn, in a field survey on December 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner position not set by original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Corner position established at the intersection of straight lines between opposing quarter corners on the perimeter of Section 30; T.47N., R.37W.

SURVEY &
MONUMENTATION

MAY 16 1997

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
At the corner position I set a 2 1/2" diameter by 30" long aluminum monument with a 3 1/4" aluminum cap with magnet stamped to read: T.47N., R.37W.; C 1/4; S-30; 1994; R.L.S. 21564 from which I established the following new blazed and scribed bearing trees and/or objects:

8"	Red Maple	N.35W.	21.28 feet
10"	Hemlock	N.60E.	9.33 feet
14"	Sugar Maple	S.48W.	18.75 feet
6'	Steel Rail	N.04E.	1.02 feet



Signed by: Richard L. Drahn

Date: February 7, 1995

Surveyor's Michigan License No. 21564