

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in HOUGHTON (County)

Located in: Corner Code #/

- 1. Public Land Survey T 47 R 37 L-11
2. Property Controlling S T R
3. Miscellaneous S T R
4. Lot No. Recorded Plat
5. Private Claims

REGISTER'S OFFICE
Houghton County, Mich.
Received for record the 25th day of April, 1994, at 9:00 o'clock, A.M. and recorded in Vol. 3, Page 227

Register of Deeds Stamp & File Number

1/4 Corner, Sections 25, 36; T.47N., R.37W.

I, Richard L. Drahn, in a field survey on December 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by E.C. Martin, U.S. Deputy Surveyor, on August 29, 1851. Original bearing trees:

- Cedar 8" S.35°W. 32 links (21.12 feet)
Cedar 10" N.58°E. 21 links (13.86 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing trees found. Re-established corner by single proportion measure on a line between the N.E. and the N.W. corner of Section 36.

SURVEY & REMONUMENTATION

MAY 16 1997


COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a standard 2" diameter by 30" long split base aluminum monument with a 3 1/2" aluminum cap stamped to read: T.47N., R.37W.; 1/4; S.25, S.36; 1993; R.L.S. 21564; from which I established the following new blazed and scribed bearing trees and/or reference objects:

- 10" Sugar Maple N.71°W. 5.76 feet
10" Red Maple N.61°E. 7.56 feet
10" Sugar Maple S.31°W. 11.74 feet

A 6' steel sign post bears: s.62°E., 0.84 feet.



Signed by Richard L. Drahn Date February 11, 1994

Surveyor's Michigan License No. 21564