

88

	Chains	Slope.	Offset
VI			120.8
	2	0	
	4	0	
VII	5	0	129.4 (3.7)
	2	0	
	4	+1	
VIII	5	-1	79.96. (4.0)
N.W. Cor. Sec 2 T48N R36W			
	2	0	(138 Ls. of random 8.62 partially)
	4	-3	Correct Not used
	5	0	
	6	0	
	8	-1	Use this →
	10	-1	
	12	0	
V	79-94.9	-1/4	Corner Common to
VIII	80		

Found Y.P. bearing tree - fallen, blaze in rotten wood on side under log. From original position of tree set a 3/4" gas pipe S 61° E 38 links. In presence of Howard Preston
Wendall Cross.
Carl Hansen.
C.M. Cade.
Dug pits two feet deep 6' E & 6' W of pipe.

NOTES FROM PAGE 89

All second growth Pines gentle rolling - Sandy soil.

Set temp Corner. Sections 2-3-34-35
Set → 44.27. offset to S. at rt. angles. to
3.47. E. Set temporary stake.

Search to south revealed a White pine post lying on side -

Stump. Y.P. N 71° W 28 L Traces of blaze.
" WP. N 55° E 15 L
" WP S 71° E 33 L * 2.3 in original
" WP. S 64° W 40 L

Set post in place for corner

3+34. Offset 141.3 links. at rt. L. to line.
Smooth even slope.