

July 3-1926.
 Transit - Cade-
 Chain - Rod. Preston
 Cross
 Ave. Hansen-
 Kaskela-

THIS APPEARS TO BE
 CONCERNING THE SW
 COR. OF SEC 11. SEE
 PAGE 82 + 83 OF FIELD
 NOTES.

D.J.C.

- offset 1 foot West.
 " 3 feet East. 2' East of line
 Through virgin hardwood.
 " 2 feet West back on line.
 Checked needle on.
 Offset 1 foot West of line.
 " $\frac{1}{2}$ " more $1\frac{1}{2}$ west of line.
 $3\frac{1}{2}$ feet East of Corner to Sections 11, 14, 15, 16.
 $1\frac{1}{2} + 3\frac{1}{2} = 5$ feet random strikes East of Corner.

At this point found an iron bar $\frac{3}{4} \times 3$
 Said by J. S. Dunham to be the corner.
 A stake by side bore names of L. C. Howe
 and L. I. Sheridan

A maple N. 55 W 98 links very old blaze-
 bore names of J. S. & H. L. Dunham 12-4-16.
 and "S" of original government markings.
 A trace of basswood 348 W 22 was found
 Buck roots and depressions were found N 28 E 17.
 This is undoubtedly the correct position
 Many trees were blazed on line north.
 The corner is at northeast corner of
 'under plus' clearing.

Offset computations on next page.