

111

Original measurements. N.W. 2 to S.W. 2 - 80.12
 S.W. 2 to S.W. 11. 80.00
 160.12.

Measure	Distance	Correction	West Offset
New measure	159.49		
Temporary $\frac{1}{4}$ West of 2	40.00	- 1	1.25
" SW of 2	80.00	- 20	2.5
" $\frac{1}{4}$ W " 11	120.00	- 47.12	3.7
Corner at SW " 11	159.49	- 63	5.00 ft.

The only known corner west of the S.W. of 2 for at least 3 miles is the SW of 4 which was set by J. S. Donham - on compass line. no bearing trees were found. It was therefore determined to set corners on a corrected line between N.W. 2 and S.W. 11 as being the most likely to place them at or near the original position.

West $\frac{1}{4}$ of 2.
 Set a $\frac{1}{2}$ " iron pipe distant 3984 chains from section corner South. Pine Stub N42E links.
 Pit 2ft x 2ft N 0 links - S 20 links.
 Point is in north track of old road.

NOTES FOR ENCL 56. ¹¹²

125.93
 30.56
 159.49
 160.12

Discrepancy .63 (2)
 31 permille

80.12
 31
 79.81
 399.9

Note This places the corner 31 links south of south bank of creek. original notes give 37.

West $\frac{1}{4}$ of 11 on line between SW corner of 2 and SW Cor of 11.
 distant 399.9 from each.
 Pealed Poplar stake - 2"
 Poplar 5" S27E 51 links.