

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>35W</u>	<u>E9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 06 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (E9) Corner common to Sections 20-21-28-29. Corner restored in 1966 by Billy D. Buckler and monumented in 1972 by A. O. Enger, RLS: "midway between two old fence lines, 25' north of fence line and in line with fence to north. Corner lies 27.5' west of a fence line running approximately south...1" ID x 18" iron pipe with 4" aluminum cap. Ash 7 S14W 82.7', Power Pole N64E 57.5' to brass washer".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E9) The 1972 monument was not recovered and presumably was removed by a road grader. Recovered an old fence line going north, a fence 25' south along the S. side of N.Laird Rd., the power pole NE with washer, and fence running approximately south, all noted in the prior record, and Enger's 1972 monumentation at the 1/16 corner and 1/4 corner to the north. The Ash NBT and fence 25' north are gone. Reestablished the corner in accordance with what I believe to be the most reliable remaining evidence, namely: 25.0' north of the E-W fence and in line with the fence going north. This position fits well, but not exactly, with Enger's monumented Section line north. The washer in the power pole bears N60E 49.2' from this position and the fence running approximately south is 18.7' East of the corner. I do not know how to account for these two differences with the record. At the position for the corner, I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped, driven to 6" below road surface. The centerline of N.Laird Rd. is about 2 ft. South of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E9) Set 1" pipe with 4" MDNR cap.
 Fd. PK/washer in power pole N60E 49.2'
 Power pole N75W 113.0' set PK/washer
 Blazed and scribed the following:
 E'ly of 4" twin cedar S30E 31.5'
 "S28 NBT"
 E'ly of triple 9" cedar S50W 41.1'
 "S29 NBT"
 Bearings are magnetic. Distances to notch in lower blaze of trees.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/26/99

For the Michigan Department of Natural Resources - Forest Management Division