

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Houghton

(County)

Located In:

Corner Code #

1. Public Land Survey

T ___ R ___
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section

S 21 T 51N R 35W 1
 S 20 T 51N R 35W 16

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

16 May 06 1999

1 Feb 19 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (1-Sec. 21) West 1/16 corner between Sections 16-21. Corner not established in the original survey. Found no subsequent record.
 (16-Sec.20) East 1/16 corner between Sections 20-29. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 21) Found no evidence of prior monumentation at the corner position. Established the corner on a line of mean true bearing between Section corner 1288.88' west and Quarter corner 1288.88' east. This position falls within the stump remains of a large W. Pine. At the position for the corner, placed a 1" IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. The corner lies on the NW side of a large gully.

(16) Found no evidence of prior monumentation at the corner position. Established the corner on a line of mean true bearing between quarter corner 1336.33' West and section corner 1336.33' East. This position falls on extension of old fence lines to north and south. At the position for the corner, I placed a 1" IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped, driven to 6" below road surface. The centerline of N.Laird Rd. is 6' south of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Set 1" pipe with 4" MDNR cap.
 Blazed and scribed the following:
 12" Y. Birch S32E 27.1' (slope) "1/16BT"
 12" W. Pine N70W 35.5' do
 7" Maple S54W 2.9' do
 18" Hemlock S16W 50.15' do
 Bearings are magnetic. Distances to notch in lower blaze.

(16) Set 1" pipe with 4" MDNR cap.
 Power Pole N82E 100.8' PK/washer
 Power Pole N68W 66.6' do
 Blazed and scribed the following:
 6" Dbl. Y. Birch S49E 46.8' "1/16S BT"
 12" Sugar S33W 48.3' do
 Bearings are magnetic. Distances are to notch in lower blaze of trees.



Signed by

Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date

8/26/99

For the Michigan Department of Natural Resources - Forest Management Division