

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Houghton  
 (County)

Located in:

Corner Code #

- |                                    |                           |           |
|------------------------------------|---------------------------|-----------|
| 1. Public Land Survey              | T <u>51N</u> R <u>35W</u> | <u>85</u> |
|                                    | T _____ R _____           | _____     |
|                                    | T _____ R _____           | _____     |
|                                    | T _____ R _____           | _____     |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____     |
|                                    | S _____ T _____ R _____   | _____     |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____     |
|                                    | S _____ T _____ R _____   | _____     |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 18 2000

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5	●											
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 (B5) Quarter corner common to Sections 7 and 18. Reestablished by proportionate methods in 1973 by A.O.Enger, RLS. 3.5" OD x 42" concrete filled iron pipe with brass cap. Y. Birch 7 S33E 7.2', Sugar Maple 10 N72E 10.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B5) Recovered the 1973 monument disturbed and damaged but at record bearing and distance from the remaining NBT Y.Birch. The Sugar NBT has been destroyed by power line clearing. Removed the 1973 monument and replaced it with a new 1"ID iron pipe capped with a 4" dia. cast aluminum MDNR tablet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B5) Set 1" pipe with 4" alum. cap.  
 Blazed and scribed:  
 11" Sugar S77E 31.4' "1/4S NBT"  
 8" Sugar S29W 7.4' do  
 20" Y.Birch N89W 67.2' do  
 13" Y.Birch S33E 7.2' (1973 NBT)  
 Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 5/2/01

For the Michigan Department of Natural Resources - Forest Management Division