

NOV 19 2003

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County) Located In: Corner Code #
1. Public Land Survey T 51N R 35W C11
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column C and row 11.

Oct 29 2003

I, Stephan J. Szyszkoski, in a field survey on 20 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C11) Corner common to Sections 29-30-31-32. 1848: Established by S.W.Higgins D.S.: North between Sections 31&32...80.00 Set post corner Secs. 29,30,31,32. Sugar 8 N10E 10, Sugar 12 S45E 20. 1913: Corner shown on Township map T51N-R35W of P.A.Larsen and M.C.Larsen as "Cedar post set from B.T." Distance west to "set post" at the East 1/16 between 30-31 is 1305'. 1972: A.O.Enger "Found an old squared and scribed post at a fence corner. Corner found in centerline of an old E-W township road, with fences running E and S... has obviously had long use as the section corner [and] it was accepted as such. Set 1"IDx36" iron pipe with 4" aluminum cap. Cedar 7 N27E 33.2', Elm 14 N45W 28.4', Y.Birch 14 S86E 14.1', Sugar 10 S41W 25.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C11) Recovered the 1972 monument, apparently disturbed from its 1972 position. It was found out of position with respect to the 1972 witness trees, three of which were recovered in good condition (The Y.Birch SE is now a rotting mound). The monument has likely been disturbed by heavy equipment, judging by the deep ruts at the corner location, and was probably reset by someone at an approximate position, being S12W 3.6' from of the position of record. Removed the monument and reinstalled it at record bearing and distance from the 1972 accessories. I found a 3/4" iron pin in the center of Uusitalo Rd. at the E1/16 corner between Sections 30 and 31, on the extension of an old fence line to the south. The pin was found 1305.88' west of C11 as reset this date, agreeing well with the 1913 record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C11) Reset the 1972 1"IDx36" I.pipe with 4" alum. MDNR cap (broken). Blazed, scribed, and set meas. nails in: 9" Hemlock S01E 16.9' "S32 NBT" The 1972 wits: 13" Cedar N29E 33.5' old blazes 11" Sugar S45W 25.8' scribing visible 16" Elm N41W 28.9' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by [Signature] Date 11/3/03
Surveyor's Michigan License No. 33986