

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>35W</u>	<u>H8</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>23</u> T <u>51N</u> R <u>35W</u>	<u>1</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

Apr 19 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (H8) Center of Section 22. Not established in the original survey.
- (1-Sec. 23) West 1/16 corner between Sections 14 and 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (H8) Established the corner at the intersection of straight lines connecting opposite quarter corners.
- (1-Sec. 23) Established the corner midway and on the Section line between Section corner 1294.38' West and Quarter corner 1294.38' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (H8) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in: | (1) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in: |
| 6" Sugar S59W 12.7' | 5" Sugar N17E 24.9' mrkd "1/16S BT" |
| 16" Sugar N26W 15.3' | 19" Cedar S70E 43.6' do |
| 9" Sugar N04W 20.6' | 5" Maple S01E 5.6' do |
| 9" Sugar N68E 18.2' | 6" Maple S78W 8.9' do |
| Set sq'd sugar post adjacent. Bearings are magnetic. Distances are to nail with tag. | Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail with tag. |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/2/06

For the Michigan Department of Natural Resources, Office of Land and Facilities