

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>35W</u>	<u>19</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>15</u>
	S <u>23</u> T <u>51N</u> R <u>35W</u>	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(19) Corner common to Sections 22-23-26-27. 1966 - Recorded by Billy D. Buckler RLS as follows: Placed iron in intersection of E-W road and old grade to north. Set 1/2" x 36" iron buried in center of E-W road. Witnesses to corner: Fence corner 32.0' north and 18.0' East, Fence corner 32.0' South and 12.0' East, Culvert 13.0' east.  
 (15-Sec. 23) West 1/16 corner between Sections 23 and 26. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(19) Recovered the 1966 monument, a 1/2" dia. rebar approx. 20" below the surface of North Laird Road. The fence corner witnesses noted in the 1966 record check approximately: N38E 39.6' to base of corner post, pushed over, S13E 33.5' to base of corner post. The culvert noted in the 1966 record is not apparent. Accepted the monument as the best available evidence of the position of the original corner. Drove a 1"IDx32" I.pipe with 4" alum. MDNR cap over the top of the monument to 8" below the surface of the road.  
 (15-Sec. 23) Established the corner midway and on the Section line between Section corner 1323.91' west and Quarter corner 1323.91' east. The position for the corner falls at the C/L-C/L intersection of Hazel Rd. to South and North Laird Rd. E-W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(19) Set 1"IDx32" I.pipe with 4" alum. MDNR cap over existing 1/2" rebar. Set measuring nails in: 9" Tamarack S44E 50.1' mrkd "S26 NBT" 9" Tamarack S07E 36.8' do 9" Tamarack S60W 55.5' "S27 NBT" N65W 84.3' Power Pole 22R39 Bearings are magnetic. Distances are to nail with tag.	(15) Set 1"IDx32" I.pipe with 4" alum. MDNR cap 6" below road surface. Set measuring nails in: Power pole 23L32 N28E 31.7' Power pole 23L33 N80E 109.2' Power pole 26W25 S06E 81.5' 13" Sugar N36W 76.1' mrkd "1/16S BT" Bearings are magnetic. Distances are to nail with tag.
---	---



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/2/06

For the Michigan Department of Natural Resources, Office of Land and Facilities