

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>35W</u>	<u>J7</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	<u>9</u>
	S <u>22</u> T <u>51N</u> R <u>35W</u>	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

9 Apr 19 2006
 J7 Apr 06 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J7) Quarter corner common to Sections 14 and 23. 1959 - Billy D. Buckler RLS remonumented the corner from one Yellow Birch B.T. stub fragment S25W 24 links with scribing plain. Set 1" pipe with 4" brass cap. Witnesses: 16" Hemlock N22 132 links W [sic], 16" Hard Maple N89W 133 links.
 (9-Sec. 22) East 1/16 corner, Section 22. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J7) The 1959 monument was not recovered. Remonumented the corner by distance-distance intersection from the 1959 NBTs, both recovered in good condition with overgrown blazes. The remonumented position is also at record bearing and distance from the remains of the OBT Y.Birch noted in the 1959 record, now a rotting stump.
 (9-Sec. 22) Established the corner midway and on a straight line between Center of Section 1317.96' west and Quarter corner 1317.96' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 18" Hemlock N14W 87.3' old blazes * 20" Sugar N84W 88.1' old scribing * 7" Sugar S58E 27.2' mrkd "1/4S NBT" 7" Sugar S58W 18.6' do Sq'd aspen post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1959 NBT.	(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 14" Hemlock N33E 23.1' mrkd "1/16S BT" 5" Sugar S31E 25.8' do 10" Y.Birch S10W 25.5' do 6" Sugar N34W 5.1' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/2/06