

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___ T ___ R ___ T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___ S 22 T 51N R 35W S 22 T 51N R 35W	6 5
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Apr 19 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20___ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (6-Sec. 22) Northeast 1/16 corner, Section 22. Not established in the original survey.
- (5-Sec. 22) North 1/16 corner, Section 22. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (6-Sec. 22) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (5-Sec. 22) Established the corner midway and on a straight line between Center of Section 1326.16' south and Quarter corner 1326.16' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (6) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
5" Sugar N08W 40.3' mrkd "1/16S BT"
15" Cedar S60E 48.1' do
6" Sugar S24E 32.5' do
7" Sugar S37W 12.7' do
Set sq'd cedar post adjacent. Bearings
are magnetic. Distances are to nail
with tag. | (5) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
6" Sugar N34E 11.8' mrkd "1/16S BT"
10" Sugar S11E 5.7' do
8" Sugar N72W 19.1' do
11" Sugar N15W 13.0' do
Set sq'd cedar post adjacent. Bearings
are magnetic. Distances are to nail
with tag. |
|--|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/2/06

For the Michigan Department of Natural Resources, Office of Land and Facilities