

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>2</u> T <u>51N</u> R <u>35W</u>	<u>J2</u>
	S <u>2</u> T <u>51N</u> R <u>35W</u>	<u>5</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3										●			
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 04/02/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J2) Center of Section 2. Not established in the original survey.

(5-Sec. 2) North 1/16 corner, Section 2. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J2) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(5-Sec. 2) Established the corner on the N-S 1/4 line of Section 2 1314.45' north of the Center of Section 2 and 1330.55' south of the North 1/4 corner of Section 2, said position being 20 chains, proportionate to the original GLO plat dimensions, north of the Center of Section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" W.Ash East 4.2' mrkd "C1/4 BT"  
 4" Sugar S05E 16.6' do  
 5" Sugar S82W 19.1' do  
 6" Elm N17W 16.9' do  
 Set cedar post adjacent. Bearings magnetic.

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 7" Maple N35E 12.35' mrkd "1/16S BT"  
 12" Hemlock S17E 30.0' do  
 4" Y.Birch S31W 17.65' do  
 4" Sugar N01W 12.45' do  
 Set cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/19/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities