

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 51N R 35W	K3
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 2 T 51N R 35W	9
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2	●	1		
3										●			
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 04/02/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K3) Corner common to Sections 1-2-11-12. Reestablished in 1969 and recorded in 1971 by A.O. Enger RLS. Set 1"IDx36" I.pipe with 4" aluminum cap at a position determined from local evidence. W.Pine 16 N60E 30.5 links, Red Maple 12 N27W 42.5 links, Sugar Maple 4 S11E 29 links.

(9-Sec. 2) East 1/16 corner, Section 2. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K3) Found the 1969 monument with broken aluminum cap, leaning slightly out-of-plumb. Plumbed the monument to be in accord with the record to the remaining two NBTs: W.Pine NE and R.Maple NW, in good condition. The Sugar NBT was not apparent. Accepted the monument as the best available evidence of the position of the original corner.

(9-Sec. 2) Established the corner midway and on a straight line between Center of Section 1299.01' west and Quarter corner 1299.01' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K3) Found 1"ID I.pipe with broken alum. cap. Set measuring nail with MDNR tag in the side of: 15" Maple N23W 28.3' old blazes (1969 NBT) 19" W.Pine N67E 21.0' do do 10" Sugar S34E 12.8' mrkd "S12 NBT" 5" Sugar N85W 12.2' "S2 NBT" Bearings are magnetic.	(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 5" Sugar N06E 24.4' mrkd "1/16S BT" 5" Sugar in clump N81E 34.6' do 3" Maple S08E 20.7' do 4" Sugar N75W 26.8' do Set sq'd cedar post adjacent. Bearings magnetic.
--	--

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 05/19/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities