


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY  
T 51N R 35W

DESCRIPTION OF CORNER Approx. Section Corner 7, 8, 17, & 18  
CORNER MONUMENT Two-sided 4" x 5' soft maple post, scribed "CIG MKR" on both sides  
DATE MONUMENT PLACED AND WITNESSED July 10, 1969  
WITNESSES TO CORNER..... Y. Birch 8 N53°W 14 lks. "WT"



Y. Birch 6 N52°E 5 lks. "WT"

Hemlock 15 S28°E 25 lks. "WT"

AND (All have a single notched blaze at base of tree,  
scribed "WT")

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This monument is intended only to mark the proportionate measured distance on a true line between Sec. Cor. 7, 12, 13, 18, T51N, R35-36W and Sec. Cor. 9, 10, 15, & 16, T51N, R35W. Former is 81.792 chains West and latter is 160.307 chains East. Found no identifiable evidence of original post or its accessories, but found a 14" Y. Birch blazed on 4 sides bearing N34½°E 90 links from chainage marker, and a 24" Y. Birch marked "7 | 8 P.R.L., H.M.L. 10/3/—" bearing S13°W 11½ links from chainage marker. Record calls for stream crossings 1.90 chains W and 4.70 chains N do not match at this point, and there seems no way to obtain these conditions in the vicinity. True corner position needs to be double proportioned between known corners N & S of it.

SURVEYOR'S SEAL

SIGNED

*Arthur C. Enger*  
REGISTERED LAND SURVEYOR

DATE

1/22/71

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68