


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY  
T 51N R 35W

DESCRIPTION OF CORNER Approx. 1/4 corner between Sections 7 and 8  
CORNER MONUMENT Two-sided 4" x 6' hard maple post, scribed "CH MKR" on both sides  
DATE MONUMENT PLACED AND WITNESSED July 10, 1969  
WITNESSES TO CORNER..... Y. Birch 6 S37½°E 9 lks. "WT"



Sugar Maple 5 N17°W 19 lks. "WT"  
Sugar Maple 10 N60°E 16½ lks. "WT"  
AND (All have a single notched blaze at base of tree,  
scribed "WT")

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This monument is intended only to mark the proportionate measured distance on a true line between Sec. Cor. 7, 12, 13, & 18, T51N, R35-36W and Sec. Cor. 9, 10, 15, & 16, T51N, R35W. Former is 41.713 chains West and latter is 200.386 chains East. Found no identifiable evidence of original post or its accessories, but found a 15" sugar maple, marked with blue tree-marking paint for approx. corner, bearing S50°W 31½ links from chainage marker. True corner position can be determined after SE corner of Section 7 has been re-established.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR

DATE

1/22/71

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68