

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 51 N.R. 35 W


Houghton COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Secs. 16-21

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 4/14/66 Distances in Feet

WITNESSES TO CORNER..... 14" Y. Birch (1/4S NBT), S 23° W, 27.0'



CIRCLE CORNER REGISTERED

14" Hard Maple (1/4S NBT), N 29° E, 33.5'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Corner from one Y. Birch Bearing tree, S 15° W, 07 lks, Tree Green blazes grown over, Several newer blazes have been chopped out.

Position checks with streams East and West, and with other corners in area.

Corner lies on East side of an old Skid Trail.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 6/3/1966
REGISTERED LAND SURVEYOR