

distances in this township tend to be shorter than the record, which supports the E & W fence line found at the 1/4 corner bet. Sec. 11 & 12, rather than Buckler's corner 1.80 chains south of it. It seems likely that Buckler's measurement along the south 1/2 mile between 11 & 12 are in error by 2 chains, due to a mistake in measuring. Note: The departure of this corner was established on line between Buckler's corner at Sec. 11, 12, 13 & 14 and corner as established by the undersigned at Sec. 1, 2, 11 & 12. (Buckler's 1/4 corner, which was 1.80 ch. S and 0.02 ch. E. of corner established here, has been obliterated.)

Found no evidence of original post or its accessories.