


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY
T 51N R 35W

DESCRIPTION OF CORNER Section Corner 20, 21, 28, and 29
CORNER MONUMENT 1" I.D. x 18" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED June 1, 1972
WITNESSES TO CORNER..... Ash 7 S14⁰W (mag.) 82.7 ft. "S29, NBT"



Power Pole N64⁰E (mag.) 57.5 ft. (To brass washer nailed to side of Pole)

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner had been restored by B. D. Buckler, R.L.S., on June 6, 1966, by reference to old fences and a county road centerline, as follows: "This corner placed midway between two old fence lines, 25' north of fence line and in line with fence to north. Corner lies 27.5' west of a fence line running approximately south." For a monument, Buckler drove a 1½"x30" iron pipe into the road. Buckler's monument apparently was heaved by frost and torn out by a road grader. Position located according to Buckler's record and a new monument installed.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Engel
REGISTERED LAND SURVEYOR
Arthur O. Engel

DATE August 21, 1972