

Corner record of B. D. Buckler dated 6/3/1966 placed corner at a found wood post. This post lies 81.49 chains southerly of the original corner on the north township boundary, or 0.70 ch. longer than the record. Additionally, it lies about 1 chain westerly of the southerly extension of the N & S fence line along the south 1/2 mile of line between Sec. 1 & 2. Further, it does not harmonize with stream crossings west of it on line between Sec. 2 & 11. Corner as placed by the undersigned shows much better, although not perfect, harmony with stream crossings between 2 & 11. In the opinion of the undersigned, neither old fences nor measurements support the found wood post, and they do support the corner reported herein. The undersigned left the wood post in place, removed Buckler's pipe monument to the position recorded here, and obliterated Buckler's new bearing trees.

Found no evidence of original post or its accessories.