


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY  
T 51N R 35W

DESCRIPTION OF CORNER 1/4 corner between Sections 15 and 16  
CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap  
DATE MONUMENT PLACED AND WITNESSED July 9, 1969  
WITNESSES TO CORNER..... Sugar Maple # S32°E 34 lks. (slope dist.) "1/4S, NBT"



Elm # N45°W 5 lks. (horiz. dist.) "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed on line between section corners 39.61 chains to north and south. Found no evidence of original post or its accessories or of any replacement monument or accessories. Corner lies on south-southeast facing slope of a high bank, trending north-northeast and south-southwest, north of the Otter River.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur P. Enger  
REGISTERED LAND SURVEYOR

DATE

1/22/71

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68