

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Houghton COUNTY
T 51N R 35W

DESCRIPTION OF CORNER 1/4 corner between Sections 9 and 10

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 1, 1969

WITNESSES TO CORNER..... Y. Birch 12 S45°E 23 lks. "1/4S, NBT"



Red Maple 10 N87°W 23 lks. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed on line between section corners 39.61 chains to north and south. Found no evidence of original post or its accessories or of any replacement post or accessories. Corner lies 42 links west of centerline of an old N and S woods road.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur P. Enger
REGISTERED LAND SURVEYOR

DATE

1/22/71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68