


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY
T 51N R 35W

DESCRIPTION OF CORNER 1/4 corner between Sections 3 and 10
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED July 2, 1969
WITNESSES TO CORNER..... Y. Birch 5 834 $\frac{1}{2}$ °W 33 lks. "1/4S, NBT"



Sugar Maple 14 N23°E 15 lks. "1/4S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed on line between section corners 39.90 chains to east and west. Found no evidence of original post or its accessories or of any replacement monument or accessories. No recorded natural features nearby with which to check corner position.

SURVEYOR'S SEAL

SIGNED Arthur P. Enger DATE 1/22/71
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing