

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY


T 51N R 35W

DESCRIPTION OF CORNER Section Corner 9, 10, 15, and 16

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 9, 1969

WITNESSES TO CORNER..... B. Ash 16 N85°W 32½ lks. "89, NBT"



B. Ash 18 S13°W 46 lks. "S16, NBT"

Red Maple 7 S35°E 34 lks. "S15, NBT"

AND

Elm 14 N70°E 42 lks. "S10, NBT"

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by double proportionate measurement from corners 1 mile N, S, and E, and 3 miles W. Found no evidence of original post or its accessories or of any replacement monument or accessories. Found old E and W line blazes on trees at the corner location.

Corner lies 85 links west of centerline of an old N and S woods road.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur C. Enger
REGISTERED LAND SURVEYOR

DATE

1/22/71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68