


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY
T 51N R 35W

DESCRIPTION OF CORNER 1/4 corner between Sections 10 and 15
CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED July 9, 1969
WITNESSES TO CORNER..... Cedar 14 S10°E 26 1/2 lks. "1/4S, NBT"



Red Maple 5 N13°W 17 lks. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed on line between section corners 40.08 chains to east and west. Found no evidence of original post or its accessories or of any replacement monument or accessories. Found a 14" cedar marked "App 1/4" with yellow tree marking paint bearing S10°E 26 1/2 lks. from corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur P. Enger
REGISTERED LAND SURVEYOR

DATE

1/22/71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68