


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY
T 51N R 35W

DESCRIPTION OF CORNER South 1/16 corner between Sections 15 and 16
CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED July 10, 1969
WITNESSES TO CORNER..... _____



Red Maple 7 N12°W 38½ lks. "1/16 S, BT"

Red Maple 7 N65°E 43 lks. "1/16 S, BT"

AND _____

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed on line between section corner 19.805 chains south and 1/4 corner 19.805 chains north. Found no evidence that the corner had ever been established previously. Corner lies on south-facing slope of a high, steep ridge running east and west.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur P. Enger
REGISTERED LAND SURVEYOR

DATE

1/22/71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68