

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY


T 51N R 35W

DESCRIPTION OF CORNER Section Corner 29, 30, 31, and 32

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 13, 1972

WITNESSES TO CORNER..... Cedar 7 N27°E (mag.) 33.2 ft. "S29, NBT"



Elm 14 N45°W (mag.) 28.4 ft. "S30, NBT"

Y. Birch 14 S86°E (mag.) 14.1 ft. "S32, NBT"

AND

Sugar Maple 10 S41°W (mag.) 25.5 ft. "S31, NBT"

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found an old squared and scribed post at a fence corner. Corner found in centerline of an old E & W township road, with fences running E and S. As it appears consistent with other corners in area, and has obviously had long use as the section corner, it was accepted as such.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE August 22, 1972